

Dorr Downtown Development Authority

August 1, 2018

Project Name: DDA Sidewalk, driveway and bench-pad replacement

Project Location: Entrance to parking lot at 1811 142nd Ave (west of Then and Now)

Specifications:

Replacement of driveway, sidewalk sections, and pad for bench and trash receptacle

Cut driveway approach in a straight line extending westward from south edge of parking lot. Remove asphalt and concrete

Cut sidewalk at joints, remove concrete

Properly dispose of broken concrete, asphalt, and debris

Prepare surfaces, add or remove sand as needed and compact as needed

Bench pad size: 4" x 12' (approximate) by 4" thick

Driveway approach size: 12' x 14' (approximate) by 6" thick

Sidewalk size: 7' x 14' (approximate) by 6" thick

Reinforcing rod to be drilled and pinned to existing good concrete slabs

Concrete mix to be 6 bag, limestone mix, and wire mesh reinforcement.

Pour and finish concrete to match adjacent concrete finish

Erect guard barriers while working and remove afterward.

Fill, restore, and seed surrounding soil as needed

Reinstall trash receptacle and bench

Bids due by Sept 1, 2018.

Bids to be delivered or sent to Dorr Township DDA, 4196 18th St, Dorr, MI 49323 in an envelope clearly marked DDA Sidewalk Sealed Bid

If approved, work to be completed by Nov 1

All work must conform to generally accepted building practices, laws, and building codes.

Dorr Township reserves the right to refuse any and all bids in its own best interest.

For further information contact Jeff Miling at 681-9874 or John Tuinstra at 681-5635